BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT39933

APPROVED SCHEDULE - B

EE/BT[illegible]BBMP/E-PMT/22/2019-20, Date: 20.01.2020

Improvements to drains of 5th cross of Pampa Extension to 13th cross road of Pampa extension in ward no 7

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )		
				In Figures		In Words
1	2318.1	Removing and refixing stone slabs of drains and pointing in CM(1:3), with all lead and left as per directions of engineer in charge of the work.	Sqm	116.85	270869.99	Rupees One Hundred Sixteen and Eighty Five Paise Only
2	727.84	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. with all lead and left as per directions of engineer in charge of the work.	Cum	144.68	105303.89	Rupees One Hundred Forty Four and Sixty Eight Paise Only
3	1465.35	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cm thick with all lead and left as per directions of engineer in charge of the work.	Sqm	779.03	1141551.61	Rupees Seven Hundred Seventy Nine and Three Paise Only
4	269.5	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks of size 400x100x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work. with all lead and left as per directions of engineer in charge of the work.	Sqm	902.56	243239.92	Rupees Nine Hundred Two and Fifty Six Paise Only
5	656.25	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.with all lead and left as per directions of engineer in charge of the work.	Sqm	1014.96	666067.50	Rupees One Thousand Fourteen and Ninety Six Paise Only
6	2160	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	998.27	2156263.20	Rupees Nine Hundred Ninety Eight and Twenty Seven Paise Only
7	6400	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.with all lead and left as per directions of engineer in charge of the work.	Nos	490.79	3141056.00	Rupees Four Hundred Ninety and Seventy Nine Paise Only
8	129.6	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . with all lead and left as per directions of engineer in charge of the work.	Cum	5677.99	735867.50	Rupees Five Thousand Six Hundred Seventy Seven and Ninety Nine Paise Only
9	2880	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. with all lead and left as per directions of engineer in charge of the work.	Sqm	41.18	118598.40	Rupees Forty One and Eighteen Paise Only
10	460	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	88.98	40930.80	Rupees Eighty Eight and Ninety Eight Paise Only

U Ramesh

Signature of the contractor

16/03

16/03

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of U RAMESH ( )		
				In Figures		In Words
11	102	KSRRB M2900-2.1. Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH with all lead and left as per directions of engineer in charge of the work.	Mtr	6274.50	639999.00	Rupees Six Thousand Two Hundred Seventy Four and Fifty Paise Only
12	11.48	Providing 100mm and down size nominal size. with all lead and left as per directions of engineer in charge of the work.	Cum	1036.90	11903.61	Rupees One Thousand Thirty Six and Ninety Paise Only
13	3.84	Providing 40mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1145.89	4400.22	Rupees One Thousand One Hundred Forty Five and Eighty Nine Paise Only
14	3.84	Providing 20mm and down size nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1145.89	4400.22	Rupees One Thousand One Hundred Forty Five and Eighty Nine Paise Only
15	2.88	Providing Fine aggrgate 2.36mm nominal size with all lead and left as per directions of engineer in charge of the work.	Cum	1106.90	3187.87	Rupees One Thousand One Hundred Six and Ninety Paise Only
16	68	Providing and fixing MS Grating 260x260 mm with all lead and left as per directions of engineer in charge of the work.	Nos	88.98	6050.64	Rupees Eighty Eight and Ninety Eight Paise Only
17	727.84	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification with all lead and left as per directions of engineer in charge of the work.	Cum	99.05	72092.55	Rupees Ninety Nine and Five Paise Only

U Ramesh

Signature of the Contractor

16/03

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/03